BRUHAT BANGALORE MAHANAGARA PALIKE

BBMP/2014-15/OW/WORK_INDENT16951

APPROVED SCHEDULE - B

EE/BTP/BBMP/E-PMT/10/2014-15, Date: 21.02.2015

Construction of rain water Harvesting (main tank) to Govt School Building at Doddabommasandra and Ramachandrapura Community Building at Ramachandrapura and Yelumandamma Badavan in ward no. 10 Vidyaranyaprua sub division.

Sl. No.	Approved Qty.	Description	Unit	Approved Tender Rates of K SHANKAR REDDY	
				In Figures	In Words
1	134.06	Earth work excavation for foundation of buildings, culverts water supply, sanitary line and electrical conduits either in pits or in trenches 1.5m and above in width, in Hard soil (ordinary soil.) not exceeding 1.5m, in depth including dressing the bottom and sides of pits and trenches, stacking the excavated soil clear from edges of excavation with lead upto 50m, after breaking of clods etc., complete and as per the directions of the Engineer-in-charge of the work	Cum	257.10	Rupees Two Hundred Fifty Seven and Ten Paise Only
2	17.6	For Main Tank Above 1.5 Mtrs Depth Add 25% Extra	Cum	321.38	Rupees Three Hundred Twenty One and Thirty Eight Paise Only
3	3.04	Providing and filling in foundation with granite / trap broken metal 100mm, and down size, with approved sand including had packing, ramming, watering, including cost of all materials and labour with all lead and lift, etc., complete and as per the directions of the Engineer-in-charge of the work	Cum	1906.76	Rupees One Thousand Nine Hundred Six and Seventy Six Paise Only
4	20.63	Providing and laying in position plain cement concrete of mix 1:4:8 with OPC cement @ 180 kgs with 40mm and down size graded granite metal coarse aggregates @ 0.85cum and fine aggregares @ 0.57 cum machine mixed, concrete laid in layers not, exceeding 15cms, thick, well compacted, in foundation and plinth, including cost of all materials, labour, HOM of machinery, curing etc., complete and as per the directions of the Engineer-in-charge of the work	Cum	4709.43	Rupees Four Thousand Seven Hundred Nine and Forty Three Paise Only
5	8.1	Providing and constructing burnt brick masonry with approved quality of modular bricks of standard size of class designation 50 (table moulded) with cement mortar 1:4 for basement and superstructure including cost of materials, labour charges, scaffolding, curing etc., complete and as per the directions of the Engineer-in-charge of the work	Cum	6531.03	Rupees Six Thousand Five Hundred Thirty One and Three Paise Only
6	296.74	Providing and removing centering, shuttering, strutting, propping etc., and removal of form work for flat surface such as roofs, landings, balconies and likes, thickness upto 200 mm including cost of all materials, labour etc., complete and as per the directions of the Engineer-in-charge of the work	Sqm	304.92	Rupees Three Hundred Four and Ninety Two Paise Only

7	42.04	Providing and laying in position reinforced cement concrete of design mix M20 with OPC cement @ 320 kgs, with 20mm and down size graded granite metal, coarse aggregates @ 0.878 cum and fine aggregates @ 0.459 cum with superplastisiser @ 3lts confirming to IS 9103-1999 reaffirmed-2008 machine mixed, concrete laid in layers not exceeding 15cms thick, vibrated for all works in foundation plinth and ground floor level for roof slabs, staircase, lintels, retaining walls, walls (any thickness) including attached plasters, column, piers, abutments, pillars, posts, struts, buttresses, string or lacing courses, parapets, coping, bed blocks, anchor blocks, plain window cills, fillets etc, including cost of all materials, labour, HOM of machinery, curing, etc., complete and as per the directions of the Engineer-in-charge of the work	Cum	5892.48	Rupees Five Thousand Eight Hundred Ninety Two and Forty Eight Paise Only
8	37.83	Providing mild steel reinforcement for R.C.C work including straightening, cutting, bending, hooking, placing in position, lapping and / or welding wherever required, tying with binding wire and anchoring to the adjoining members wherever necessary complete as per design (laps, hooks and wastage shall not be measured and paid) cost pf materials, labour, HOM of machinery etc., complete and as per the directions of the Engineer-in-charge of the work	Qtl	7749.82	Rupees Seven Thousand Seven Hundred Forty Nine and Eighty Two Paise Only
9	130.72	Providing and fixing plaster mesh 200mm wide manufactured out of hot dipped galvanished iron of nominal thickness 0.35mm with a zinc coating of 120gms per sqm width, along route of walls chipped for services, junction between and brick walls including cost materials, labour, for fixing complete as per specifications. (length of mesh only be measured for payment.) etc., complete and as per the directions of the Engineer-in-charge of the work	m	47.22	Rupees Forty Seven and Twenty Two Paise Only
10	36.64	Providing 15m thick cement plaster in single coat with cement mortar 1:3,tobrick masonry including rounding off corners wherever reuired smooth rendering, Providing and removing scaffolding, including cost of materials, labour. Curing etc., complete and as per the directions of the Engineer-in-charge of the work	Sqm	194.14	Rupees One Hundred Ninety Four and Fourteen Paise Only
11	36.64	Extra for providing and mixing water proofing compound in cement plaster work at one kg per bag or in the proportion recommended by the manufactures, for cement mortar 1:3, 20mm thick cost of materials etc., complete and as per the directions of the Engineer-in-charge of the work	Sqm	12.87	Rupees Twelve and Eighty Seven Paise Only
12	18.32	Providing 20mm thick cement plaster in single coat with cement mortar 1:3, to stone masonry & concrete surface including rounding off corners wherever required smooth rendering, : Providing and removing scaffolding, including cost of materials, labour, curing etc., complete and as per the directions of the Engineer-in-charge of the work	Sqm	246.61	Rupees Two Hundred Forty Six and Sixty One Paise Only
13	0.16	Supply and Providing Aggregate 40 mm and below etc., complete and as per the directions of the Engineer-in-charge of the work	Cum	792.00	Rupees Seven Hundred Ninety Two Only
14	0.16	Supply and Providing Aggregate 20 mm and below etc., complete and as per the directions of the Engineer-in-charge of the work	Cum	990.00	Rupees Nine Hundred Ninety Only
15	0.16	Supply and Providing Sand etc., complete and as per the directions of the Engineer-in-charge of the work	Cum	1435.50	Rupees One Thousand Four Hundred Thirty Five and Fifty Paise Only
16	100	Providing PVC Rain Water Pipes and Fittings ISI Standards 4" Single socket Pipe 110 mm dia etc., complete and as per the directions of the Engineer-in-charge of the work	M	858.33	Rupees Eight Hundred Fifty Eight and Thirty Three Paise Only

17	13	Providing PVC Rain Water Pipes Specials Plain Bend etc., complete and as per the directions of the Engineer-in-charge of the work	M	159.39	Rupees One Hundred Fifty Nine and Thirty Nine Paise Only
18	8	Plain Tec	M	339.57	Rupees Three Hundred Thirty Nine and Fifty Seven Paise Only
19	1	Relevant Plumbing accessories for inlet and outlet with out FFL including Filter etc., complete and as per the directions of the Engineer-in-charge of the work	No.	8910.00	Rupees Eight Thousand Nine Hundred Ten Only
20	1	1HP Submersible centrifugal force pump of approved make with all necessary fittings including wiring switch board, starter etc., and Electronic Automatic Equipment (Programmable Logic Control) etc., complete and as per the directions of the Engineer-in-charge of the work	mtr	17820.00	Rupees Seventeen Thousand Eight Hundred Twenty Only
21	3	Square Tank Cover "ISI" marked 24'x24x pf 100kg in weight etc., complete and as per the directions of the Engineer-in-charge of the work	No.	4958.91	Rupees Four Thousand Nine Hundred Fifty Eight and Ninety One Paise

H. Sankar Reddy
Signature of the Contractor

Executive Engineer
Byarayanapura Division
BBMP, Bangalore - 92